# KPS & KASS Update

10st October 2022





#### Overview of KPS

**Objectives** 

# Providing high-precision PNT information required in the era of the 4th industrial revolution

Goals

#### **Development and construction of KPS system**

that stably provides PNT services to meet various satellite navigation needs



Program

KPS R&D Program (including Space, Ground and User Segment)

Period

2022~2035 (14 years)


Governing



R&D



# **KPS System Configuration**



#### **KPS Segments**



- 3 GEO Satellites
- 5 IGSO Satellites
- Payloads : Navigation, Time-sync., SBAS, and SAR



- Operation Centers
- Satellite Control Centers
- Antenna Stations
- Monitoring Stations
- Mission Control Stations



- Research and Development Receiver
- Reference Station Receiver
- Test and Evaluation Receiver
- User Receivers

## **KPS Development Plan**

System Design ('22~'24)

- SDR/PDR/CDR of KPS system
- International cooperation for orbits, frequencies, sites acquisition
- Navigation signal and constellation design

System
Development
('25~'28)

- Development of satellite bus and payloads
- Development of satellite control center and antenna station
- Launch of the 1st IGSO satellite in 2027


Deployment and Validation ('29~'35)

- Development and launch of the 4 IGSO and 3 GEO satellites
- Development of all of the ground segment
- Test during IOC and FOC

# KASS Status (1)

### **Main Goal**


- Provide APV-I SoL Service to Airports located in South Korea
- Start APV-I SoL Service after 2023



# KASS Status (2)

### KASS 1<sup>st</sup> Satellite Launch

- (Satellite) Malaysian Measat-3D launch with KASS payload
- (Date) 23rd June in 2022
- (Vehicle) Ariane 5 ECA+
- (Launch Location) Ariane Launch Area 3, Kourou, French Guiana
- (GEO Location / Lifespan) 91.5 ° E / 15 years



# KASS Status (3)

#### **Status**

- ('21.6) KUS Infrastructure Facilities Construction Completion
- ('22.6.23.) KASS 1st GEO satellite (Measat-3D with KASS payload) launch
- ('22.7.4.~6.) KASS Navigation Payload IOT (In Orbit Test) Completion
- ('22.7.19.) KASS FAT (Factory Acceptance Test) Completion

# Future Plan

- ('22.10.~11.) KUS ↔ GEO#1 (Measat-3D) integration test
- ('22.12.) KASS 1st signal broadcasting (MTO/0)
- ('23.6.) KASS 2<sup>nd</sup> signal broadcasting (MT0/0 or MT0/2)
- ('23.11.) SQR (System Qualification Review)

	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023	2024	
Development & Implementation (KPO)		System Design					System IVQ				System Operation Support	
									1 <sup>st</sup> GEO launch	\$QR (`23.4Q	SoL Service ) (TBD)	

<sup>\*</sup> KPO: KASS(Korean SBAS) Program Office \* KUS: KASS Uplink Station

# **GNSS Application in Korea**

# Various areas including ICT, Transportation, Commerce, and Safety



















